

1 040694  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-8

API NUMBER 15-185-22,869-000 249 n  
SW SE NE, SEC. 33, T. 25 S, R. 11 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3180

2970 feet from S section line  
990 feet from E section line

Operator: Deutsch Oil Company  
Name & Address: 107 N. Market, Suite 1115  
Wichita, KS 67202

Lease Name Helmer Well # 1-33  
County Stafford 133.25  
Well Total Depth 4100 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 264

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Company, Inc. License Number 5929  
Address 304 W. Central, Wichita, KS 67202

Company to plug at: Hour: 11:30 a.m. Day: 8 Month: 9 Year: 19 92

Plugging proposal received from John Armbruster  
(company name) Duke Drilling Co. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe  
1st plug at 600' with 50 sx cement, 2nd plug at 270' with 75 sx cement,  
3rd plug at 40' with 15 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 12:45 p.m. Day: 8 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,  
2nd plug at 270' with 75 sx cement,  
3rd plug at 40' with 15 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.  
Water well plugged with 5 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

(If possible, observe this plugging.)

DATE 10-13-92  
INV. NO. 36432

Signed Stephen J. Pugh  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 10 1992  
CONSERVATION DIVISION  
WICHITA, KANSAS

OCT 28 1992

FORM CP-2/3  
REV 01-81

EFFECTIVE DATE: 8-30-92

State of Kansas

185-22,869

FORM MUST BE SIGNED ALL BLANKS MUST BE FILLED

DISTRICT #

NOTICE OF INTENTION TO DRILL

55A7 X Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date September 5, 1992 month day year

OPERATOR: License # 3180 DEUTSCH OIL COMPANY Name: 107 North Market - Suite 1115 Address: Wichita, Kansas 67202 City/State/Zip: Contact Person: Kent Deutsch Phone: 316/267-7551

CONTRACTOR: License #: 5929 Name: DUKE DRILLING CO., INC.

Well Drilled For: Well Class: Type Equipment: X Oil Enh Rec X Infield X Mud Rotary Gas Storage Pool Ext. Air Rotary OGW Disposal Wildcat Cable Seismic: # of Holes Other

If OGW: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location:

Exp. 2/25/93

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq. It is agreed that the following minimum requirements will be met:

Pusher: John Ambush SPUD DATE: 9-2-92 INIT. JAW LENGTH SURFACE PLANNED: 200' RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 10 3/4" @ 265' CONDUCTOR ANHYDRITE T- B- ELEVATION WTD 4100' FORMATION Kinderhook RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ Ft. W/ SX 1 1/2 Base Anyht @ 600 Ft. W/ 50 SX 2 1/2, 122 Plug @ 270 Ft. W/ SX Bottom Surface @ 40 Ft. W/ 15 SX RAT HOLE CIRC/W/SX MOUSE HOLE W/10 SX WATER WELL S SX (Irr. Well Pond Hauling) TECHNICIAN PR DATE 9-7-92 TYPE OF CEMENT 60/40 p.d. 6% S.P. did see STARTING TIME 11:30 (AM/PM) DATE 9-8-92 COMPLETION TIME 12:45 (AM/PM) DATE 9-8-92 CEMENT COMPANY Allied

RECEIVED KANSAS CORPORATION COMMISSION

RECEIVED KANSAS CORPORATION COMMISSION

AUG 20 1992

CONSERVATION DIVISION WICHITA, KS

Complete - Loss Circulation @ 2605'