

1-051692

7-7

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,914-0000

NW NE NW, SEC. 27, T. 25 S, R. 11 W X

330 feet from N E section line

1650 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Teichman Well # 1

Operator: Raymond Oil Company, Inc.

County Stafford 134.42

Name

Address P.O. Box 48788

Well Total Depth 4136 feet

Wichita, KS 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 254

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 12 p.m. Day: 7 Month: 7 Year: 19 93

Plugging proposal received from John Armbruster

(company name) Duke Drilling Company (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 600' with 50 sx cement, 2nd plug at 280' with 60 sx cement,

3rd plug at 40' with 15 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:50 p.m. Day: 7 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,

2nd plug at 280' with 60 sx cement,

3rd plug at 40' with 15 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by United.

RECEIVED STATE CORPORATION COMMISSION

INVOICED

If additional description is necessary, use BACK of this form

JUL 13 1993

I (XXX / did not) observe this plugging.

DATE 7-28-93

WV. NO. 38219

Signed Richard W. Lacey CONSERVATION DIVISION
Wichita, Kansas (TECHNICIAN)

EFFECTIVE DATE: 7-6-93
DISTRICT # 1
SEA? Yes

State of Kansas 185-22,914
NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date July 14 1993
month day year

Spot SW NE NW Sec 27 Twp 25 S. Rg 11 East West

OPERATOR: License # 5046
Name: Raymond Oil Company, Inc.
Address: P.O. Box 48788
City/State/Zip: Wichita, KS 67201
Contact Person: Rat Raymond
Phone: (316) 267-4214

330' feet from North line of Section
1650' feet from West line of Section
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License # 5929
Name: Duke Drilling Co.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Stafford County
Lease Name: Teichman Well #: 1
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:
X Oil ✓ ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OUVO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes ... Other
If OUVO, old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Is this a Propped/Spaced Field? ... yes X no
Target Formation(s): Lansing, Miss, Viola
Nearest lease or unit boundary: 330'
Ground Surface Elevation: Est. 1850' feet MSL

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no
Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 200'
Surface Pipe by Alternate: X 1 ... 2
Length of Surface Pipe Planned to be set: 240'
Length of Conductor pipe required: N/A
Projected Total Depth: 4350
Formation at Total Depth: Viola
Water Source for Drilling Operations:
... well ... farm pond X other

OUR Permit #: _____
Will Cores Be Taken?: ... yes X no
If yes, proposed zone: _____

Exp. 1/1/94

AFFIDAVIT

240' Alt. I Req.

Pusher John Ambuster INIT. mlw

SPUD DATE 7-1-93

LENGTH SURFACE PLANNED 240'-10"

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbbls. when done bbbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 1 1/4" @ 254 CONDUCTOR
ANHYDRITE T- B- ELEVATION

TD 4136 FORMATION Viola

RAN PIPE @ SX DV TOOL SX ALT II DONE Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 600 Ft. W/ 50 SX

1/2 Base Anyh. @ Ft. W/ SX

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ 280 Ft. W/ 60 SX

40' Plug @ 40 Ft. W/ 15 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond)
TECHNICIAN R.L. DATE 7-6-93 Hauling

TYPE OF CEMENT per 2 b page 1

STARTING TIME 7:00 AM DATE 7-7-93

COMPLETION TIME 3:30 (PM) DATE 7-7-93

CEMENT COMPANY United

RECEIVED
CONSERVATION DIVISION
Wichita, Kansas
DATE 7-7-93 TIME 3:30 (PM)