

1070109

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-21,663-0000
NW NE SW SEC. 32, T 25 S, R 11 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME RUNDELL WELL # 1-32

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD

140.17

OPERATOR LICENSE # 3498

WELL TOTAL DEPTH 4313 FEET

OPERATOR: GILBERT C RUNDELL

PRODUCTION CSG: SIZE 4 1/2" @ 4258' WITH 175 SX

NAME AND RR 1 BOX 120

SURFACE CASING: SIZE 8 5/8" @ 277' WITH 175 SX

ADDRESS STAFFORD, KS 67578

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31528

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 30 MONTH: 11 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MONTE ANDREWS

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 3954-64

SAND BACK TO 3900' AND 4 SX CEMENT ON TOP WITH BAILER. PUMP 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - WIPER PLUG - 125 SX CEMENT. MAXIMUM PRESSURE AT 100#. SHUT IN WITH 0#.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 10:45 AM DAY: 30 MONTH: 11 YEAR: 1999

ACTUAL PLUGGING REPORT _____

SAND BACK TO 3900' AND PUT 4 SX CEMENT ON TOP WITH BAILER. PUMP 300# HULLS ~~RECEIVED~~ GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - WIPER PLUG - 125 SX CEMENT.
KANSAS CORPORATION COMMISSION

MAXIMUM PRESSURE AT 100#. SHUT IN WITH 0#.

DEC 03 1999

12-8-99

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1800' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 12/21/99

SIGNED

[Signature]
(TECHNICIAN)

FORM CP-2/3

NV. NO. 061007