

1 050665

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-22302-0000

SWSWSE, SEC. 32, T. 25 S, R. 11 (W) <sup>R</sup>

330 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Rundell "B" Well # 1

Operator: TXO Production Corp  
Name & Address: 155 N. Market Suite 1000  
Wichita, KS 67202

County Stafford 138.13

Well Total Depth 4250 feet <sup>Kinderhook</sup>

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Aldebaran Drilling Co Inc License Number 5829

Address 453 S. Webb Road, Suite 100, Box 18611 Wichita KS

Company to plug at: Hour: 3:00 pm Day: 10 Month: November Year: 1985 <sup>67207</sup>

Plugging proposal received from Rex. Crauens.

(company name) TXO Production Corp (phone) \_\_\_\_\_

were: To fill hole with heavy mud + spot plugs through  
drill pipe. 1st plug @ 1250' w/50sx of cement

2nd plug @ 400' w/50sx of cement

3rd plug @ 40' w/solid bridge + 10sx

Circulate Rathole w/15sx Circulate Mousehole w/10sx

Anhydrite (1200) Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:15 pm Day: 10 Month: November Year: 1985

ACTUAL PLUGGING REPORT Kept hole full of heavy mud + spotted plugs

through drill pipe 1st plug @ 1250' w/50sx of cement

2nd plug @ 400' w/50sx of cement

3rd plug @ 40' w/solid bridge + 10sx

Circulated Rathole w/15sx of cement

circulated Mousehole w/10sx of cement

Remarks: Halliburton pumped 60/40 poz mix 6% gel cement  
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE NOV 22 1985

NOV 14 1985

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 11163