

To: ¹ 040646 4-15
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,809-0000
165' W of
NW NE-NE, SEC. 32, T. 25 S, R. 11 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5822
Operator: VAL Energy, Inc.
Name & Address
P.O. Box 322
Haysville, KS 67060

63 R
4950 feet from S section line
1155 feet from E section line
Lease Name Nelson Well # A1
County Stafford
Well Total Depth 4155 135.03 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 244

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor VAL Energy, Inc. License Number 5822
Address P.O. Box 322, Haysville, KS 67060

Company to plug at: Hour: 8:30 a.m. Day: 15 Month: 4 Year: 19 92

Plugging proposal received from Joe Stallard
(company name) VAL Energy, Inc. (phone) 316-522-1560

Work: 5 1/2" at 4152' w/200 sx cement, PBT 4152', Perfs at 3938-41, 3949-52, 3966-74, 3956-62,
1st plug set CIBP at 3550' and dump 2 sx cement on top; 3588-92, 3608-10, 3714-16'
2nd plug pump down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 10 3/4" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:25 a.m. Day: 15 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3550' and dumped 2 sx cement on top through bailer,
2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 150 sx cement.
Maximum pressure 200 psi and shut in 50 psi.

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1992
4-11-92
Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2696' of 5 1/2" casing.
(If additional description is necessary, use BACK of this report.)

INVOICED
Observe this plugging.

DATE 4-28-92
INV. NO. 35095

Signed Stephen J. Pfeifer
(TECHNICIAN)