

To: 1 040651 4-24
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,302-00-01

SW SW SE, SEC. 32, T. 25 S, R. 11 W/E
330 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Rundell C OWWO Well # 3

Operator: Raymond Oil Company, Inc.

County Stafford 138.09

Name & Address P.O. Box 48788

Well Total Depth 4249 feet

Wichita, KS 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 a.m. Day: 24 Month: 4 Year: 19 92

Plugging proposal received from Manny Boatwright

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4246' w/175 sx cement, Perfs at 3995-4013', 4084-4100'

1st plug sand back to 3940' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 24 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3827' and dumped 5 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 300 psi and shut in 100 psi. (Note: After pumping 3 sx hulls, 10 sx gel,
50 sx cement, 10 sx gel, 1 sx hulls, plug and 20 sx cement, plug container blew out & 8 5/8"
waited on welder.)

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2925' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
~~VOID~~ observe this plugging.

DATE 5-6-92

INV. NO. 35171

Signed Stephen J. Pfeiffer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
5-1-92