

To: 1 040814
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-15

API NUMBER 15- 185-22,753-0000

SW SW NW, SEC. 34, T 25 S, R 11 W XX
2970 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046
Operator: Raymond Oil Company, Inc.
Name & Address: P.O. Box 48788
Wichita, KS 67201-8788

Lease Name Rundell Well # D-1
County Stafford
Well Total Depth 4120 133.90 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 15 Month: 12 Year: 19 93

Plugging proposal received from David Brady

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

4 1/2" at 4113' w/150 sx cement, Perfs at 3988-4021'

1st plug sand back to 3930' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 15 Month: 12 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3940' and dumped 4 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 275 psi.

RECEIVED STATE CORPORATION COMMISSION

DEC 22 1993

Remarks: Used 60/40 Pozmix 6% gel by United Cementing & Acid Co. Recovered 2530' of casing (if additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 12-30-93

INV. NO. 39606

Signed Stephen J. Peifer (TECHNICIAN)