

1 030599

API NUMBER 15- 185-22,304-0000

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NW SE NW, SEC. 9, T 25 S, R 11 W/E

3630 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422  
Operator: Abercrombie Drilling, Inc.  
Name & Address: 801 Union Center  
Wichita, KS 67202

Lease Name Chester Well # 1  
County Stafford 129.35  
Well Total Depth 3980 Viola feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 30 Month: November Year: 19 85

Plugging proposal received from Harvey Moore

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 568  
Elevation 1805

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 40 sx cement

3rd plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement,

6th plug to circulate mouse hole with 5 sx cement. Plug water well from bottom to top with 5 sx cement  
Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30 am Day: 30 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 580' with 50 sx cement, 2nd plug at 370' with 40 sx cement, 3rd & 4th plugs - solid bridge- hulls - plug at 40' -- cement to surface with 10 sx cement. 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 5 sx cement, and plugged water well with 5 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan # 279238  
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION

Signed Steve Blumenthal  
(TECHNICIAN)

DATE DEC 11 1985

DEC 5 1985

V. NO. 11401  
11-30

CONSERVATION DIVISION

FORM CP-2/3  
Rev. 01-84

CARD MUST BE TYPED

State of Kansas  
NOTICE OF INTENTION TO DRILL  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 11 11 85  
month day year

API Number 15- 185-22,304

OPERATOR: License # 5422  
Name: Abercrombie Drilling, Inc.  
Address: 801 Union Center  
City/State/Zip: Wichita, KS 67202  
Contact Person: Jack L. Partridge  
Phone: 316-262-1841

C. NW SE. NW... Sec. 9... Twp. 25. S, Rge. 11...  
3630 Ft North from Southeast Corner of Section  
3630 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse slide)

CONTRACTOR: License # 5422  
Name: Abercrombie Drilling, Inc.  
City/State: Wichita, KS

Nearest lease or unit boundary line 330 feet.  
County: Stafford  
Lease Name: Chester Well# 1  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Depth to Bottom of fresh water 100 feet  
Lowest usable water formation Cedar Hills  
Depth to Bottom of usable water 200 feet  
Surface pipe by Alternate:  2  
Surface pipe to be set 300 feet  
Conductor pipe if any required None feet  
Ground surface elevation 1805 feet MSL  
This Authorization Expires 5-1-86  
Approved By 10-31-85

If OWWO: old well info as follows:  
Operator  
Well Name  
Comp Date Old Total Depth  
Projected Total Depth 4100 feet  
Projected Formation at TD Viola  
Expected Producing Formations Lansing, Viola

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to C.C. specifications.

Signature of Operator or Agent: Jerry A. Langrehr  
Title: Executive Vice President  
Date: 10-30-85  
Form C-1 4/84

320' 8 5/8"

MOVE-IN 11-21-85

yes, will

60/40 P. 22 1990

PUSHER	Marvey Moore	FORMATION	Viola	STARTING TIME & DATE	11-30-85	COMPLETION TIME & DATE	10:30 AM	1st PLUG @	580	FT. W/	50	SX
TD	3980	SURFACE PIPE	8 5/8 @ 340					2nd PLUG @	370	FT. W/	40	SX
ANHYDRITE	565	ELEVATION	1805					3rd PLUG @	3640	FT. W/	10	SX
								4th PLUG @		FT. W/		SX
								RAT HOLE CIRCULATED	W/	10		SX
								MOUSE HOLE CIRCULATED	W/	5		SX
								WATER WELL PLUGGED	W/	5		SX
								CEMENT COMPANY	Sum	279 238		
								TECHNICIAN	SP			

50SX - 50SX  
40SX - 40SX  
40' Soilbridge - 10 SX  
Rat - 10SX - 60/40 P. 22  
Moore - 5SX  
Circulate in U.S. Cen. D. 17

STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas