

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23063-00-03
Spot: SESESE Sec/Twnshp/Rge: 10-25S-11W
330 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: CRAVENS Well Number: 1
County: STAFFORD Total Vertical Depth: 4050 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: 155 N. MARKET - SUITE 800 PO BOX 48
WICHITA, KS 67201

Conductor Pipe: Size feet: 8/31.63
Surface Casing: Size 8.625 feet: 252 225 SX CMT
Production: Size 5.5 feet: 4048 WITH 280 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/07/2002 2:45 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: PUMP BOTTOM PLUG 400# HULLS & 50 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT WITH 100# HULLS MIXED IN. 2ND PLUG AT 280' WITH 50 SX CMT WITH 100# HULLS MIXED IN. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 06/07/2002 3:45 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 3700'. PERFS AT 2811-16'. PUMPED DOWN 5 1/2" CASING WITH 400# HULLS & 50 SX COMMON CMT. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT WITH 100# HULLS MIXED IN. 2ND PLUG AT 280' WITH 50 SX CMT WITH 100# HULLS MIXED IN. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
JUN 17 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2420' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED JUN 12 2002

DATE

6-18-02

INV. NO.

2002061968 NP

Form 10-2/3