

15-185-11892-0002

1 040409

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Operator: Rama Operating Co., Inc.
Name & Address P.O. Box 159,
Stafford, Ks. 67578

3-22 143
API NUMBER 15- Docket # D-15,339

CSWNW, SEC. 10, T 25 S, R 11 WE

3300 feet from S section line

4620 feet from E section line

Lease Name McCune Well # 1

County Stafford 139.75

Well Total Depth 4300 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 265

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well X O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, Ks. 67524

Company to plug at: Hour: 2:00 P.M. Day: 22 Month: 3 Year: 19 90

Plugging proposal received from Milard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 6 5/8" at 4127' PBTD = 4300' Open Hole at 4130' to 4300'

1st plug - Pump 100 sx. of common cement

2nd plug - Pump 400# hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, release 8 5/8"

wiper plug and pump 125 sx. cement

Plugging Proposal Received by Mike Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:45 P.M. Day: 22 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug - pumped 100 sx. of common cement

2nd plug - pumped 300# hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 100# hulls,

released 8 5/8" wiper plug and pumped 125 sx. cement.

Maximum Pressure = 500# and shut in 50#

Remarks: used 60/40 poz mix 6" gel by Allied. Recovered 1660' of 6 5/8" casing
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-6-90
INV. NO. 27807

APR 02 1990
4-2-90
CONSERVATION DIVISION
Wichita, Kansas

Signed Stephen J. Puffer
(TECHNICIAN)