

15-185-01096-0000

1 120979

10-7

API NUMBER 15- Drilled 5/17/60

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW SW, SEC. 10, T 25 S, R 11 W&E

2310 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Lease Name Post Well # 1

Operator: RAMA Operating Co., Inc.

County Stafford

Name & Address P.O. Box 159

Well Total Depth 4118 ^{133.83} feet

Stafford, KS 67578

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage License Number 31529

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 7 Month: 10 Year: 1994

Plugging proposal received from Vernon Duntz

(company name) Mike's Testing & Salvage (phone) 316-938-2943

were: 5 1/2" at 4099' w/200 sx cement, Perfs at 3453-60'

1st plug sand back to 3400' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 5 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10 a.m. Day: 7 Month: 10 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3400' and dumped 5 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

5 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-600 psi and shut in 450 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1400' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

observe this plugging.

RECEIVED STATE CORPORATION COMMISSION CONSERVATION DIVISION WICHITA, KANSAS OCT 18 1994

Signed [Signature] (TECHNICIAN)

INVOICED DATE 11-3-94 INV. NO. 41574