

9-20

To: 1 061136
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,212-0000
NW NW NE, SEC. 23, T 25 S, R 13 W/EX

4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086
Operator: Pintail Properties
Name & Address: 412 East Douglas, Suite 1
Wichita, KS 67202

Lease Name Reissig "A" Well # 1
County Stafford 138.91
Well Total Depth 4274 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 392

Abandoned Oil Well Gas Well _____ Input Well _____ D&A _____

RECEIVED
STATE CORPORATION COMMISSION

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address Box 698, Great Bend, KS 67530
SEP 22 1988

Company to plug at: Hour: 1:15 p.m. Day: 20 Month: Wichita, Kansas Year: 19 88

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4250' PBD 4220' Perfs at 3676-81'

1st plug sand back to 3625' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 20 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3625' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 600 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2247' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (If used) observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 10-6-88

INV. NO. 22530