

1 090376

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,266-0000

NE NE NW, SEC. 23, T 25 S, R 13 W/E

4950 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6393

Lease Name Dudrey "A" Well # 1

Operator: Brougner Oil, Inc.

County Stafford 139.43

Name & Address P. O. Drawer 1367

Well Total Depth 4290' Arbuckle 37' feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 397

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mohawk Drilling, Inc. License Number 6394

Address Box 1362, Great Bend, KS 67530

Company to plug at: Hour: 8:00 am Day: 11 Month: September Year: 1985

Plugging proposal received from Wilbur Cotton

(company name) Mohawk (phone) 316-792-4531

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 669-788' Elevation 1919 GL

1st plug in the Arbuckle with 40 sx cement if in the Arbuckle 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug at 425' with 40 sx cement solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Robert B. Tarbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 11:00 am Day: 11 Month: September Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 780' with 50 sx cement; 2nd plug at 420' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary use BACK of this form.)

INVOICED

DATE SEP 17 1985

INV. NO. 10106

STATE CORPORATION COMMISSION

SEP 16 1985

Signed R. B. Tarbutton (TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

CARD MUST BE TYPED

State of Kansas  
**NOTICE OF INTENTION TO DRILL**  
(see rules on reverse side)

*yes*  
CARD MUST BE SIGNED

Starting Date: 8-28-85  
month day year

API Number 15-185-22,266

OPERATOR: License # 6393  
Name BROUGHER OIL, INC.  
Address P. O. Drawer 1367  
City/State/Zip Great Bend, KS 67530  
Contact Person Joe E. Brougher  
Phone 316-793-5610

NE NE NW See 23 Twp 25 S, Rge 13  East  
(location)  West  
4950 Ft North from Southeast Corner of Section  
2970 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6394  
Name MOHAWK DRILLING, INC.  
City/State Great Bend, KS

Nearest lease or unit boundary line 330' N & E feet.  
County Stafford  
Lease Name DUDREY "A" Well# 1  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Depth to Bottom of fresh water 200 feet  
Lowest usable water formation Dakota  
Depth to Bottom of usable water 300 feet  
Surface pipe by Alternate: 1  2   
Surface pipe to be set 375 feet  
Conductor pipe if any required  
Ground surface elevation Unknown feet MSI.  
This Authorization Expires 2-12-86

If OWWO: old well info as follows:  
Operator  
Well Name  
Comp Date Old Total Depth  
Projected Total Depth 4300 feet  
Projected Formation at TD Arbuckle  
Expected Producing Formations Simpson, Kansas City & Arbuckle

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

date 8-9-85 Signature of Operator or Agent *Joe E. Brougher* Title President  
Approved By *8-12-85* *K*  
RECT-SORKOHE

*Wulber Cotton - 9578-345-9-7-85*

RECEIVED  
STATE CORPORATION COMMISSION

SEP 16 1985

CONSERVATION DIVISION  
Wichita, Kansas