

To: 1 120812  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-2 API NUMBER 15-185-21,915-0000  
NW SW NW, SEC. 20, T 25 S, R 13 W AX

3630 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6050

Lease Name Garner A Well # 1  
County Stafford 141.79

Operator: Kelso Casing Pulling, Inc.  
Name:  
Address P.O. Box 347  
Chase, KS 67524

Well Total Depth 4363 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 374

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 2 Month: 8 Year: 1993

Plugging proposal received from Mike Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

work: 5 1/2" at 4362' w/150 sx cement, Perfs at 4264-83'  
1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 1:45 p.m. Day: 2 Month: 8 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 5 sx cement on top of sand  
through bailer,  
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Pumping pressure 0-600 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

I would like to observe this plugging.

DATE 8-17-93  
REV. NO. 38362

Signed Duane Rankin  
(TECHNICIAN)

AUG 11 1993