

To: 1120811 8-2
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200, COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,992-0000
NW NW NW, SEC. 20, T 25 S, R 13 WXX
4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6050
Operator: Kelso Casing Pulling, Inc.
Name & Address: P.O. Box 347
Chase, KS 67524

Lease Name Garner A Well # 2
County Stafford
Well Total Depth 4355 141.53 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 424

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 2 Month: 8 Year: 19 93
Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2943

was: 5 1/2" at 4354' w/300 sx cement, Perfs at 4258-68'
1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 12 p.m. Day: 2 Month: 8 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 5 sx cement on top of sand
through bailer,
2nd plug pumped into 8 5/8" surface casing with 250 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 150 lbs. hulls and 100 sx cement.
Pumping pressure 0-600 psi and shut in 200 psi.
Welded plate & 5 1/2" collar on 8 5/8".

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (holder) ~~XXXXXX~~ observe this plugging.
DATE 8-17-93
INV. NO. 38363

Signed Duane Rankin
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1993