

To: **1041124**
STATE CORPORATION COMMISSION
Wichita State Office Bldg. **11-27** PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 185-22,186-0000
SW SW SW, SEC. 17, T 25 S, R 13 W/EX
330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30852
Operator: KLM Operating
Name: KLM Operating
Address P.O. Box 155
Belpre, KS 67519

Lease Name "B" Garner Well # 2
County Stafford
Well Total Depth 4320 140.40 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 470

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9:45 a.m. Day: 27 Month: 11 Year: 19 95

Plugging proposal received from Richard McIntyre

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

logs: 5 1/2" at 4319' w/175 sx cement, PBTD 4250', Perfs at 4253-63'

1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,

2nd plug at 840' with 50 sx cement,

3rd plug at 450' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 a.m. Day: 27 Month: 11 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4186' and dumped 5 sx cement on top of sand
bridge through bailer, Spotted plugs through 5 1/2" casing with gel spacer between plugs:

2nd plug at 840' with 50 sx cement,

3rd plug at 500' with 50 sx cement,

4th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

12-1-95 DEC - 1 1995

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2166' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 12-4-95

INV. NO. 44178

Signed Stephen J. Pfeiffer
(TECHNICIAN)