

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-121-02652-0000
 Spot: SESWNE Sec 33 Twp 16 S Rng 23 E / W
2836 Feet from N / S Line of Section
1754 Feet from E / W Line of Section
 GPS: Lat: 38.614680 Long: 94.869990 Date: 9/24/15 - 2/12/15
 Lease Name: Wehmeir Well #: WEH 01
 County: Miami Total Vertical Depth: 290 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>SURF - Casing</u>	<u>8.000</u>	<u>20</u>	<u>0</u>	
Address 1: <u>266 N. Main St. Ste. 266</u>	<u>PROD - Casing</u>	<u>2.000</u>	<u>270</u>	<u>0</u>	
Address 2: _____					
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - <u>1513</u>					

Well Type: OG - Oil & Gas (OIL) UIC Docket No.: _____ Date/Time to Plug: 8/20/15 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Revd from: Mike Kepney Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report: Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: ZERO - None
 Date/Time Plugging Completed: 8/20/15 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Move equipment to location. Clear around well. Loosen plug to let pressure off well. Found 2" pipe under plug. Run 1" and reamer to 274 ft. Pull out. Run 1" and tap to 290 ft. Pull out. Run 1" and overshot to 290 ft and hit. Pull out with nothing on it. Probably TD. Perforate well. Run 1" back and wash and hit at 290 ft. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 14 sacks of cement. Well plugged.		<u>75</u>	<u>250</u>	<u>CSG - Casing</u>

Remarks: Contract No. 38595. Control No. 20150041-001. GPS'ed NAD 83 by F. G. Reg. Sect.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03
 Received
 KANSAS CORPORATION COMMISSION
OCT 01 2015
 CONSERVATION DIVISION
 WICHITA, KS
Frank Guilfoyle
 (Technician)
 Form: District Plugging Report - _____