

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-121-02653-0000
 Spot: SWSWNE Sec 33 Twp 16 S Rng 23 E / W
2848 Feet from N / S Line of Section
2143 Feet from E / W Line of Section
 GPS: Lat: 38.614720 Long: 94.871350 Date: 9/24/15 2/12/15
 Lease Name: Wehmeir Well #: WEH 02
 County: Miami Total Vertical Depth: 295 feet

Operator License No: 101 String DRIVE - Drive Pipe Size 8.000 Depth 10 Pulled 0 Comments EST.
 Op Name: STATE OF KANSAS
 Address 1: 266 N. Main St. Ste. 266
 Address 2: _____
 City: WICHITA
 State: KS Zip Code: 67202 - 1513

Well Type: OG - Oil & Gas (oil) UIC Docket No.: _____ Date/Time to Plug: 8/20/15 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Revd from: MIKE KEPLEY Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: ZERO - None
 Date/Time Plugging Completed: 8/20/15 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Move equipment to location. Clear around well. Run 1" to 100 ft inside Drive Pipe and hit mud. Wash 1" to 295 ft and hit hard. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 91 sacks of cement. Well plugged.	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____

Remarks:

Contract No. 38595. Control No. 20150041-002. GPS'ed NAD 83 by F. G. Reg. Sect.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 Received KANSAS CORPORATION COMMISSION FRANK GUILFOYLE (Technician)
OCT 01 2015 Form: District Plugging Report - _____
 CONSERVATION DIVISION WICHITA, KS