


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit.
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Stafford County, Sec. 27 Twp. 25 Rge. 13 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE SW SW
Lease Owner Specter Pipe & Supply, Inc.
Lease Name Gobin Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed Sept. 17, 1967 19
Application for plugging filed April 28, 1969 19
Application for plugging approved April 29, 1969 19
Plugging commenced 5-26-69 19
Plugging completed 6-4-69 19
Reason for abandonment of well or producing formation failure to produce profitably.
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation Kansas City Depth to top 3714 Bottom 3973' Total Depth of Well 4325 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	306'	none
				4 1/2"	3913'	3013'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3700' with sand, pumped 5 sacks cement, mudded to 300', set 19' rock bridge, pumped 25 sacks cement, mudded to 40', set 10 rock bridge, dumped 10 sacks cement to top.

RECEIVED
STATE CORPORATION COMMISSION
JUN 16 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing Pulling Co.
Address Rt. 4, Great Bend, Kans.

STATE OF Kansas, COUNTY OF Russell, ss.

Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mark Specter
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June, 1969

My commission expires May 21, 1971

Wilma M. Lindahl
Notary Public.

38312

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COPY

COMPANY **W. F. Newton**
 FARM **Gobin** NO. **1**

SEC. 27 T. 25 R. 13W
 LOC. NE SW SW

TOTAL DEPTH **4325**
 COMM. **Sept. 5, 1967** COMP. **Sept. 17, 1967**
 SHOT OR TREATED
 CONTRACTOR **Woodman & Iannitti Drilling Company**
 ISSUED **11-18-67**

COUNTY **Stafford**
 KANSAS



CASINO
 20 10
 15 8 5/8 @ 306' cem w/ 200 sx
 12 6
 13 5 4 1/2" @ 3930' cem w/ 150 sx

ELEVATION **1931' KB**

PRODUCTION **30 BOPD PLUS 57% W/**
Lans 3850-55

FIGURES INDICATE BOTTOM OF FORMATIONS

40	Sand	TOPS: LOG	
200	Sand	Anhydrite	787
260	Red Bed & Sand	Base Anhydrite	815
290	Red Bed	Heebner	3524
307	Red Bed & Shale	Toronto	3544
788	Red Bed	Douglas	3568
815	Anhy	Brown lime	3686
1150	Shale	Lansing	3714
1710	Shale	Base Kansas City	3973
1760	Broken Lime	Mississippi	4091
1975	Lime	Kinderhook	4147
2150	Lime & Shale	Viola	4163
2305	Lime	Simpson Shale	4288
2445	Lime	Simpson Dolomite	4293
2650	Lime		
2855	Lime & Shale		
2985	Lime		
3133	Lime		
3275	Lime		
3372	Lime		
3475	Lime		
3580	Lime		
3676	Lime		
3720	Lime		
3790	Lime		
3846	Lime		
3865	Lime		
3880	Lime		
3920	Lime		
3970	Lime		
4010	Lime		
4065	Lime		
4106	Lime		
4140	Lime & Chert		
4143	Lime		
4199	Lime & Chert		
4240	Lime & Chert		
4258	Lime & Chert		
4294	Lime		
4325	Lime		

RECEIVED
 STATE CORPORATION COMMISSION
APR 28 1969
 CONSERVATION DIVISION
 Wichita, Kansas

I certify the above to be a true and correct copy of the driller's log and the geological tops to the best of my knowledge and belief.

Woodman & Iannitti Drilling Company

K. T. Woodman