


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 1 Twp. 25 Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines NE SE SW
Lease Owner Aylward Drilling Company
Lease Name Bowker "B" Well No. 1
Office Address 813 First National Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed July 21, 19 60
Application for plugging filed March 13, 19 63
Application for plugging approved March 14, 19 63
Plugging commenced March 15, 19 63
Plugging completed March 18, 19 63
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production March 15, 19 63
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Mississippi Depth to top 4040 Bottom 4075 Total Depth of Well 4213 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	226'	None
				4 1/2"	4157'	2100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with chat from 4157 feet to 4039 feet and
dumped three sacks cement.
Set 15-foot rock bridge at 200 feet, dumped five sacks
cement with dump bailer. Bailed fluid down and dumped
20 sacks.
Mud hole to 40 feet, set 5-foot rock bridge and dumped
10 sacks.

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kent Well Servicing Company
Address Box 470, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Charles D. Williams (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

813 1st Nat'l Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of April, 1963

My commission expires December 11, 1965

DUANE JESSUP

Notary Public.

BOWKER "B" NO. 1

Casing Record:	Company: Aylward Drilling Company	Location: NE SE SW Sec.1-25-14W
8 5/8" - 226'	Contractor: Aylward Drilling Company	Stafford County
4 1/2" - 4157'	Commenced: July 12, 1960	Kansas
	Completed: July 21, 1960	Elevation: 1962 R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	160	Set 8 5/8" surface pipe @ 226' w/215 sacks cement.
Sand and Clay	160	170	
Shale, Black	170	226	
Shale	226	995	Geological Tops: (Log)
Anhydrite	995	1020	
Shale & Shells	1020	1720	Heebner 3508
Shale & Lime	1720	1850	Toronto 3528
Lime & Shale	1850	1910	Douglas 3546
Lime w/very little Shale	1910	2100	Brown Lime 3647
Lime	2100	2210	Lansing 3678
Lime & Shale	2210	2420	Mississippian 4040
Shale w/Lime	2420	2465	Kinderhook 4098
Shale & Lime	2465	2695	Viola 4170
Shale w/some Lime	2695	2810	T.D. 4211
Shale & Lime	2810	3020	
Lime with shale	3020	3100	DST 3680-3830 Open 1 hr. Fair Blow
Shale	3100	3105	Rec. 1680' S.W. IBHP 1293# - FBHP 1285#
Shale w/Lime	3105	3310	FP 367#-995#.
Shale & Lime	3310	3320	
Sandy Lime	3320	3415	DST 3836-3935 Open 30" - Weak blow/14" died
Sand, Lime & Shale	3415	3647	Rec. 62' Rotary mud w/few specks oil.
Lime	3647	3915	IBHP 1414#/20" - FBHP 1318#/15"
Lime w/some Shale	3915	3935	FP 110#-120#.
Lime	3935	3962	
Lime & Chat	3962	4035	DST 4014-65 Open 1 hr. Good Blow.
Chat	4035	4065	Rec. 45' mud.
Chert	4065	4076	IBHP 183#/20" - FBHP 496#/30"
Shale	4076	4080	FP 45#-270#.
Shale, Lime & Chert	4080	4120	
Cherty Lime w/Shale	4120	4153	Set 4 1/2" casing @ 4157' w/88 sacks cement.
Lime & Chert	4153	4213	T.D.

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1963

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Charles O. Williams

Subscribed and sworn to before me this 25th day of July, 1960

Duane Jessup
Notary Public

My commission expires December 11, 1961