


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County, Sec. 1 Twp. 25s Rge. 14w (#) (W)

Location as "NE/CNW/SW" or footage from lines NW SE NE.
Lease Owner PETROLEUM, INC.
Lease Name GOODMAN "B" Well No. 2
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed FEBRUARY 12 1959
Application for plugging filed JULY 31 1959
Application for plugging approved AUGUST 3 1959
Plugging commenced AUGUST 10 1959
Plugging completed AUGUST 17 1959
Reason for abandonment of well or producing formation CASING PARTED, UNABLE TO COMPLETE PRODUCIBLE ZONES
If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT, 222 S. MAIN, ST. JOHN, KANSAS
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 4292 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	256'	NONE
				5-1/2"	4289'	3100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

CASING COLLAPSED AT 3167', COULD NOT REACH BOTTOM, PLACED 10 SACKS OF CEMENT AT 3167'. PULLED 3100' 5-1/2" OD CASING, PUMPED IN 35 SACKS OF CEMENT AND LET SET 24 HOURS, BAILED HOLE DOWN TO 56' AND PUMPED IN 35 SACKS OF CEMENT TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SOUTHWEST CASING PULLING COMPANY, INC.
Address BOX 364, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 18TH day of AUGUST, 19 59

My commission expires APRIL 14, 1963

Arthur J. Wiles
Notary Public.

PLUGGING
FILE SEC. 1, T. 25, R. 14W
BOOK PAGE 59, LINE 19

WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 1 T. 25S R. 14W

FARM GOODMAN "B" NO. 2


LOC. NW, SE, NE

TOTAL DEPTH 4292'

COUNTY STAFFORD CO., KANSAS

COMM. January 14, 1959 COMP. January 28, 1959

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 256' W/250 sax.
5 1/2" @ 4289' W/225 sax.

ELEVATION 1953' DF

PRODUCTION Plugged & Abandoned

FIGURES INDICATE BOTTOM OF FORMATIONS

50	Surface soil, shale & sand
246	Shale & sand
848	Shale & shells
920	Anhydrite
1160	Shale & shells
1850	Shale
3475	Shale & lime
3745	Lime & shale
3925	Lime
3950	Lime & shale
4080	Lime
4123	Lime & chert
4220	Cherty lime
4289	Lime & chert
4292	Lime
4292	T. D.

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1959

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #2 GOODMAN "B" well

Subscribed and sworn to before me this 3rd day of April 19 59

My Commission Expires: July 11, 1960 **PLUGGING**

FILE SEC. 1 T. 25S R. 14W
BOOK PAGE 57 LINE 19

NOTARY PUBLIC