


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Stafford County. Sec. 2 Twp. 25S Rge. (E) 14 (W)
Location as "NE/CNW&SWK" or footage from lines NE NE NE
Lease Owner Sterling Drilling Company
Lease Name Bowker Well No. 2
Office Address Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 13, 19 58
Application for plugging filed July 13, 19 58
Application for plugging approved July 13, 19 58
Plugging commenced July 13, 19 58
Plugging completed July 13, 19 58
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4248 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	320'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud. Set bottom plug at 240' with 20 sacks cement.
Set top plug at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

7-16-58 JUL 16 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet.)

Name of Plugging Contractor Group Exploration Company
Address Sterling, Kansas

STATE OF KANSAS COUNTY OF RICE, ss:
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Sterling, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of July, 19 58

Charles M. Hall
Notary Public.

My commission expires Jan. 6; 1962

PLUGGING
FILE SEC 2 T 25 R 14W
BOOK PAGE 115 LINE 21

GROUP EXPLORATION COMPANY
Sterling, Kansas

WELL LOG-----BOWKER #2

Location: NE NE NE, Section 2-25S-14W
Stafford County, Kansas

OWNER: Ten Well Partners
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 6-30-58
COMPLETED: 7-13-58

TOTAL DEPTH: 4248'

LOG

0-160	Sand
160-865	Shale & Red Bed
865-890	Anhydrite
890-975	Red Bed
975-1485	Red Bed & Salt
1485-1700	Shale
1700-1930	Shale & Lime
1930-2115	Lime
2115-2295	Lime & Shale
2295-2710	Lime
2710-3285	Shale & Lime
3285-3490	Lime
3490-3664	Shale & Lime
3664-3954	Lime
3954-4004	Shale & Lime
4004-4045	Mississippi
4045-4055	Shale
4055-4060	Lime
4060-4107	Shale
4107-4245	Lime
4245-4248	Lime & Chert T.D.

CASING RECORD

Ran 320' of 8-5/8" casing set with
225 sacks pozmix, 2% calcium chloride.

PRODUCTION

Plugged & Abandoned

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1958

CONSERVATION DIVISION
Topeka, Kansas

PLUGGING
FILE SEC 2 T. 25 R. 14W
BOOK PAGE 115 LINE 27