

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 2 Twp. 25 Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines NE NW NW

Lease Owner WILKINSON DRILLING, INC.

Lease Name BOWKER Well No. 1

Office Address 1121 Union National Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4/5/ 19 58

Application for plugging filed 4/4/ 19 58

Application for plugging approved 4/4/ 19 58

Plugging commenced 4/5/ 19 58


Plugging completed 4/5/ 19 58

Reason for abandonment of well or producing formation As no commercial quantity of oil and/or gas was encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Mr. Broadfoot

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4238' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Sand</u>	<u>Water</u>	<u>0</u>	<u>130</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud, plug at 279' topped with 1/4 sack Hulls, 15 sks cement through drill pipe; mud to 20' plug at 20' topped with 1/4 sack Hulls, 5 sks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor WILKINSON DRILLING, INC.

Address 1121 Union National Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Walter M. Wilkinson (Signature) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter M. Wilkinson

1121 Union National Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 19 58.

Barbara F. Moore
Notary Public.

My commission expires January 2, 1961

PLUGGING
SEC 2 T. 25 R. 14W
BOOK PAGE 92 LINE 37

WILKINSON DRILLING, INC.
1121 Union National Building
Wichita 2, Kansas

May 28, 1958

BOWKER NO. 1

Company	- WILKINSON DRILLING, INC.	Location	- NE NW NW, Sec. 2-25-14W
Contractor	- Company Tools		Stafford County, Kansas
Commenced	- March 22, 1958	Elevation	- 1950' KB
Completed	- April 5, 1958	Casing	- 16 jts. 8 5/8"
Total Depth	- 4238 feet		

FIGURES INDICATE BOTTOMS OF FORMATIONS

Depth	Formation
0 - 130	Sand
130 - 275	Shale and Sand Streaks
275 - 317	Red Beds
317 - 860	Shale and Shells
860 - 890	ANHYDRITE
890 - 1830	Shale and Shells
1830 - 2045	Shale and Lime
2045 - 2220	Lime and Shale
2220 - 3622	Shale and Lime Streaks
3622 - 3983	Lime with Shale Streaks
3983 - 4020	White Tripolitic Chert
4020 - 4030	Shale
4030 - 4040	Chert
4040 - 4102	Shale
4102 - 4133	Dolomite and Chert
4133 - 4148	Shaley Dolomite
4148 - 4212	Dolomitic Chert
4212 - 4220	Shale
4220 - 4238	Dolomite and Chert

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Bowker No. 1, located in the NE NW NW, Section 2 - 25 - 14W, Stafford County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Weckhusen

Subscribed and sworn to before me this twenty-eighth day of May, nineteen hundred and fifty-eight.

Carolyn F. Moore

My Commission expires January 2, 1961.

RE
STATE CORP. COMMISSION

JUN 3 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING			
FILE	SEC	T	R
	2	25	14W
BOOK	PAGE	LINE	
	92	37	