

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15 - 155 - 20,709-000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Frank J. Black OPERATORS LICENSE NO. 5357

ADDRESS P. O. Box 250, McPherson, KS 67460 PHONE # (316) 241-2582

LEASE (FARM) Doles WELL NO. 1 WELL LOCATION NE NE SW COUNTY Reno

SEC. 30 TWP. 25 RGE. 4 (S) or (W) TOTAL DEPTH 4060' PLUG BACK TD 3246'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 257' CEMENTED WITH 175 SACKS

CASING SIZE 5-1/2" SET AT 4059' CEMENTED WITH 200 SACKS

PERFORATED AT 3227 - 3232

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Sand to 3175' and dump 5 sacks cement.

Bail hole and set bridge at 300' and fill with Redi-Mix.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Frank J. Black

RECEIVED
STATE CORPORATION COMMISSION
PHONE # (316) 241-2582

ADDRESS P. O. Box 250, McPherson, KS 67460 OCT 29 1987

PLUGGING CONTRACTOR Nicholas Casing Pulling LICENSE NO. 6698
Wichita, Kansas

ADDRESS Box 108, Geneseo, KS 67444 PHONE # (316) 824-6467

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Frank J. Black
(Operator or Agent)

DATE: 10-29-87

②

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

THIS NOTICE

FEB 02 '88

EXPIRES

November 2, 1987

WELL PLUGGING NOTICE

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

Doles #1
NE NE SW
Sec. 30-25S-04W
Reno County

Frank Black
P. O. Box 250
McPherson, KS 67460


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,



Shari Feist
Director
State Corporation Commission

DISTRICT #2 . 202 W. First, Ste. 300, Wichita, KS 67202 (316) 263-8809



Blackstone Drilling, Inc.

Box 1184 523 West Kansas Phone (913) 241-1250
McPHERSON, KANSAS 67460

NOV. 17, 1980

COMPANY: FRANK J. BLACK
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: DOLES #1
 LOCATION: NE NE SE Section 30-25-4W,
 Reno County, Kansas
 COMMENCED: November 5, 1980
 COMPLETED: November 24, 1980
 ELEVATION:

0	to	165	Red Shale
165	to	261	Shale
261	to	1390	Shale & Lims
1390	to	1515	Shale
1515	to	2365	Shale & Lims
2365	to	2940	Lims & Shale
2940	to	3275	Lims
3275	to	3390	Shale & Lims
3390	to	3510	Lims & Shale
3510	to	3560	Lims
3560	to	3621	Mississippi
3621	to	3825	Lims
3825	to	3895	Lims & Shale
3895	to	4010	Shale
4010	to	4060	Lims
		4060	T. D.

Core 12" hole to 257' and run 259' of 8 5/8" surface pipe, cemented with 175 sacks of cement at 257'. Plug down at 10:15 A. M., November 6, 1980. Run 8070' of 3 1/2" casing, cemented with 100 sacks of cement at 4059', 1 foot off bottom. Plug down at 7:00 P. M., November 16, 1980.

TIPS:

Measurements taken from E. A.

CERTIFICATE

I, P. E. Ploffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of your Doles #1, located on the NE NE SE Section 30-25-4W, Reno County, Kansas this as reflected by the files of Blackstone Drilling, Inc.

[Signature]
 P. E. Ploffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 17th day of November, 1980.

[Signature]
 Johnnie L. Schmidt - Notary Public

JOHNNIE L. SCHMIDT
 McPherson County, Kansas
 My Appl. Exp. June 23, 1986