

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-155-20741-0000 (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Coastal Oil & Gas Corporation OPERATORS LICENSE NO. 6593
73102

ADDRESS One Leadership Square, Suite 1700, Okla. City, OK PHONE # (405) 239-7031

LEASE (FARM) Vincent Lubbers WELL NO. 1 WELL LOCATION C NW SW COUNTY Reno

SEC. 16 TWP. 26S RGE. 8W (M) or (W) TOTAL DEPTH 4325 PLUG BACK TD 3450

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 317 CEMENTED WITH 300 SACKS

CASING SIZE 4 1/2 SET AT 3454 CEMENTED WITH 200 SACKS

PERFORATED AT 3370-3374

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Dump sand plug capped w/5 sx. cmt @ 3360,
POOH w/2-3/8" tubing, perf 4-1/2" casing @ 325'. Circulate 92 sx. 60/40 Poz cmt in 4-1/2" csg &
annulus from 325' to 3' cut off 8 5/8 & 4 1/2 csg 3' BGL.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACC-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Don DeHerrera 3-14-87 MAA PHONE # (913) 252-3271

ADDRESS Box 126, Holyrood, KS 67450 CONSERVATION DIVISION
Wichita, Kansas

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. 5287

ADDRESS 1100 E. 8th, Hays, KS 67601 PHONE # (913) 625-3431

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: C. Paul Couch
(Operator or Agent)

DATE: 3-6-87

(2)

Schlumberger

SIMULTANEOUS
**COMPENSATED NEUTRON
FORMATION DENSITY**

COUNTY RENO
FIELD WILDCAT
LOCATION SEC. 16-26S-8W
WELL VINCENT LUBBERS NO. 1
COMPANY CINCO EXPLORATION & DIAMOND SHAMROCK

COMPANY CINCO EXPLORATION & DIAMOND SHAMROCK
WELL VINCENT LUBBERS NO. 1
FIELD WILDCAT
COUNTY RENO STATE KANSAS

LOCATION C-NW-SW
API SERIAL NO. 16 SEC. 26S TWP. 8W

Other Services:
DLL-GR

Permanent Datum: GROUND LEVEL; Elev.: 1643
Log Measured From K.B., 5 Ft. Above Perm. Datum
Coring Measured From K.B.

Elev.: K.B. 1648
D.F. 1643
G.L. 1643

Date	1-8-81						
Run No.	ONE						
Depth-Driller	4325						
Depth-Logger	4327						
Btm. Log Interval	4326						
Top Log Interval	1000						
Casing-Driller	8 5/8 @ 317			@	@	@	@
Casing-Logger							
Bit Size	7 7/8						
Type Fluid in Hole	SALT						
Dens.	Visc.	9.5	4.5				
pH	Fluid Loss	6.6	6.6 ml		ml		ml
Source of Sample	MUD PIT						
Rm @ Meas. Temp.	.117 @ 74 °F	.082 @ 108 °F	@ °F	@	@	@	@
Rmf @ Meas. Temp.	.085 @ 74 °F	.060 @ 108 °F	@ °F	@	@	@	@
Rmc @ Meas. Temp.	@ °F	@ °F	@ °F	@	@	@	@
Source: Rmf	Rmc	14					
Rm @ BHT	.082 @ 108 °F	@ °F	@ °F	@	@	@	@
Circulation Stopped	1300						
Logger on Bottom	2000						
Max. Rec. Temp.	1.08 °F				°F		°F
Equip. Location	7749 WICHITA						
Recorded By	WARREN						
Witnessed By	DEUTSCH						

RECEIVED
STATE COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1288

THIS NOTICE
JUN 10 '87
EXPIRES

March 10, 1987

WELL PLUGGING NOTICE

Vincent Lubbers #1
C NW SW
Sec. 16-26S-08W
Reno County

Coastal Oil & Gas Corporation
One Leadership Square, Ste. 1700
Oklahoma City, OK 73102

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely, ..

Jack McCord, Director

Please contact the district office to review your suggested method of plugging

DIST. #2 200 Colorado Derby Bldg., 202 W. 1st Street, Ste. 300, Wichita, KS 67202
five days prior to plugging the well (KAR-82-3-113). (316) 263-8809