

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County, Sec. 9 Twp. 25S Rge. 11 (X) (W)

Location as "NE/CNW/SW" or footage from lines C SW/4 NE/4

Lease Owner R. P. Nixon

Lease Name Vogel Well No. #1

Office Address 754 East Wichita, Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 30 19 62

Application for plugging filed November 30 19 62

Application for plugging approved November 30 19 62

Plugging commenced November 30 19 62

Plugging completed November 30 19 62

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Herman Justus

Producing formation Depth to top Bottom Total Depth of Well 3935 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	254 1/2	Cmtd w/275 sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill with mud to 180 ft. 1/4 sack hulls.

Plugg 10 sacks cement through drill pipe.

Fill w/mud to 40 ft. 1/4 sack hulls, dump

12 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 16 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Company, Inc.

Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

R. P. Nixon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

754 East Wichita, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of January, 19 63

Ruth E. Miller

Notary Public.

My commission expires January 5, 1965






Shields

Russell, Kansas

WELL LOG

Operator: R. P. Nixon
 Well: Vogel #1
 Commenced: November 19, 1962
 Completed: November 30, 1962
 Contractor: Shields Drilling Company, Inc.

Well Description: SW NE
 Sec. 9-25S-11W
 Stafford County, Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	254 1/2'	Cmtd w/275 sax

Elevation: 1,810' RB

Treatment:

Production: D & A

Tops:

Heebner	3,259'
Toronto	3,276'
Brown Lime	3,420'
Lansing-KC	3,445'
Mississippi	3,787'
Viola	3,917'

..... Figures Indicate Bottom of Formations

Sand & Shale	255'
Shale & redbed	450'
Redbed, shale & sand	1,200'
Shale	1,439'
Anhydrite	1,452'
Shale & shells	1,630'
Shale & lime	3,457'
Lime	3,860'
Shale	3,917'
Lime	3,935' RTD

NOTES

DST #1	3,424'-3,457'	Tool open 1 hr. w/good blow thruout. Recovered 6' mud. No pressures.
DST #2	3,460'-3,487'	Tool open 1 hr. Recovered 6' mud. No pressures.
DST #3	3,522'-3,540'	Tool open 1 hr. Recovered 65' muddy wtr. IBHP-950#, FBHP-750#/20 min.
DST #4	3,919'-3,927'	Tool open 30 min. Recovered 15' mud. No pressures.
DST #5	3,927'-3,935'	Tool open 1 hr. w/gas to surface in one minute. Recovered 150' free oil, 660' gassy oily water, 400' water. IBHP-600#, IFP-150#, FFP-400#, FBHP-550#/20 min.

JAN 16 1963

CONSERVATION DIVISION
Wichita, Kansas