


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 9 Twp. 25 Rge. 11 E/W
Location as "NE/CNW/SW" or footage from lines
C NE SE

Lease Owner Ervin Schneider
Lease Name Barr #1 Well No.
Office Address Pratt, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole)



Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12/11/79 19
Plugging completed 12/15/79 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owen
Producing formation Depth to top Bottom Total Depth of Well 3930
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	253	none
				5 1/2"	3925	2434'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 3900' and ran 5 sacks cement. Shot pipe at 3010', 2820', 2600', 2415', worked pipe loose and pulled 73 joints. Squeezed hole with 4 sacks hulls, 25 sacks gel, 4 sacks hulls, released plug and displaced with 125 sacks 50-50 pozmix, 4% gel and 3% cc.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of Dec., 19 79

Margaret Melcher
Notary Public.

My commission expires



RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1979

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED OCT 24 1979

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


Company- K. P. NIXON
Farm- Barr No. 1

SEC. 9 T. 25 R. 11W
C NE SE

ERVIN SCHNEIDER

County Stafford
KANSAS

Total Depth. 3930'
Comm. 11-27-61 Comp. 12-8-61
Shot or Treated.
Contractor. Shields Drilling Co., Inc.
Issued. 9-22-62



Elevation. 1797'

Production. 49 BOPD, 80% W

CASING:

8 5/8" 253' cem w/275 ex.
5" 3925'

Figures Indicate Bottom of Formations.

sand	80
gravel, redbed, shale & shells	253
redbed & shells	750
shale, shells & salt	1430
anhydrite	1445
shale & shells	1730
lime	1830
lime & shale	3434
lime	3930 RTD
Total Depth	

TOPS: SCOUT

Heebner	3245
Toronto	3260
Brown Lime	3401
Lansing	3428
Viola	3908

RECEIVED
STATE CORPORATION COMMISSION

NOV 05 1979

CONSERVATION DIVISION
Wichita, Kansas