

STATE OF KANSAS
OIL AND GAS COMMISSION
S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-185-23063-0000²

LEASE NAME Cravens

WELL NUMBER A-1

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 10TWP.25S RGE. 11W(E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 6-6-02

Plugging Completed 6-10-02

RECEIVED

JUN 15 2002

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RAYMOND OIL COMPANY, INC.

ADDRESS P.O. Box 48788 Wichita, Kansas 67201

PHONE (316) 264-4214 OPERATORS LICENSE NO. 5046

Character of Well Gas

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

A plugging proposal was approved on _____ (date)

Richard Lacey (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4050'

Log depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	252'	None
				5-1/2"	4048'	2420

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from _____ feet to _____ feet each sack. Pumped bottom with 50 sacks cement and 200# of hulls and displaced to 2600'. Shot pipe loose @2420', pulled up to 600', pumped 10 sacks gel, 50 sacks cement, pulled up to 270', pumped 50 sacks cement and 100# hulls, pulled up to 40' and pumped 20 sacks cement, 60/40 pos, 67 gel. Plugging Complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Raymond Oil Company, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

do hereby certify that the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of June 2002

Notary Public

My Commission Expires: _____

