

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,939-0000

LEASE NAME McCune

WELL NUMBER #1

SPOT LOCATION C NW NW

SEC. 10 TWP. 25 RGE. 11 (X) (W)

COUNTY Stafford

Date Well Completed 2-26-84

Plugging Commenced 2-26-84

7:00 AM

Plugging Completed 8:30 AM,

2-26-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TXO Production Corporation
200 West Douglas - Suite 300
ADDRESS Wichita, Kansas 67202

PHONE # (316) 265-9441 OPERATORS LICENSE NO. 5171

Character of Well Dry
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 3990'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	309'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. Heavy mud to 600';
50 sacks at 600'; 50 sacks at 360'; Bridge, 1 sack
hulls, wooden plug, & 10 sacks at 40'. 10 sacks in rathole; 5 sacks
in water well. 125 sacks 60/40 Pozmix, 2% gel and 3% cc.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor STERLING DRILLING COMPANY License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well and that the same are true and
correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) Richard L. Mead
STERLING DRILLING COMPANY

(Address) P. O. Box 129, Sterling, Ks.

MAR 07 1984

SUBSCRIBED AND SWORN TO before me this 28th day of February, 1984.

Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85



STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- McCUNE #1
Located: C NW NW, Section 10-25S-11W, Stafford County, Kansas

OWNER: TXO Production Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 18, 1984
COMPLETED: February 26, 1984

TOTAL DEPTH: 3990'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 115 Sand and Clay	Ran 7 joints 8 5/8" OD casing. 296.65'
115 - 311 Red Bed	pipe set at 309' K.B. Cemented with
311 - 1280 Shale	150 Sacks Lite and 100 sacks Common,
	2% gel and 3% cc. Plug down at 6:15 PM,
	2-18-84, by Sun Cementing.
1280 - 1550 Shale and Lime Stringers	
1550 - 3935 Lime and Shale	
3935 - 3990 Lime	Plugged.

Deviation Surveys: 3/4° at 1731'
1 1/4° at 3490'
1 1/2° at 3990'

RECEIVED
STATE CORPORATION COMMISSION

MAR 07 1984

CONSERVATION DIVISION
Wichita, Kansas