


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 10 Twp. 25 Rge. 11W (E) (W)
Location as "NE/CNW%SW%" or footage from lines C SW NW
Lease Owner Robert L. Jones & R. D. Olson
Lease Name McCune Well No. 1
Office Address 353 Armour Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed 19__
Application for plugging filed 19__
Application for plugging approved 19__
Plugging commenced 19__
Plugging completed FEBRUARY 27, 19 65
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 3550' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

263' of 8 5/8" surface pipe, cement circulated. Fluid level in the hole was at 103'. 1st cementing plug and 1/4 sack of hulls was pushed in fluid to 240', and cemented with 25 sacks, through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged solid with hulls and dry cement on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1965

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Terrel Drilling & Production
Address Box 606 Russell, Kansas

STATE OF KANSAS, COUNTY OF Sedgewick, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) X Albert P. Jones
353 ARMOUR, WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 1965

My commission expires 11-5-67 Deward S. Greedy Notary Public.

WELL LOG

COMPANY **W. C. MC BRIDE, INC.**

SEC. 10 T. 25S. R. 11W

FARM **MC CUNE** NO. **1**


LOC. **C-SW, NW**

TOTAL DEPTH **4130'**

COUNTY **STAFFORD CO., KANSAS**

COMM. **December 3, 1960** COMP. **December 16, 1960**

CONTRACTOR **GARVEY DRILLING COMPANY**



CASING **8 5/8" @ 263' w/225 sax.**

ELEVATION **1799' DF**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

263	Sand & shale
450	Shale & shells
540	Shale
590	Anhydrite
1176	Shale & anhydrite streaks
1560	Shale & shells
1780	Lime & shale
2500	Lime
2710	Lime & shale
3035	Shale & lime
3150	Lime & shale
3240	Lime
3325	Lime & shale
3415	Shale
3923	Lime
4015	Viola
4045	Lime & shale
4085	Lime
4130	Arbuckle
4130	T. D.

CHECK NUMBER
87042
 ISSUED

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 17 1965
 CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS }
 County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 MC CUNE well

Verne A. Morris

Subscribed and sworn to before me this 23rd day of December 1960

My Commission Expires: April 14, 1963

Arthur J. Miles
 NOTARY PUBLIC