


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Stafford County, Sec. 23 Twp. 25 Rge. 13W (E) (W)  
Location as "NE/CNW/SW" or footage from lines E/2 NW NE  
Lease Owner Clinton Oil Company  
Lease Name Reissig #2 - D Well No.  
Office Address Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed Jan. 20 19 71  
Application for plugging filed Oct. 31 19 72  
Application for plugging approved Nov. 1 19 72  
Plugging commenced 2/8/73 19  
Plugging completed 2/19/73 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production December 10 72  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation Arbuckle Depth to top 4235 Bottom 4253 Total Depth of Well 4253 Feet  
Show depth and thickness of all water, oil and gas formations. (open hole)

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
* Arbuckle	Oil	4229	4261	8-5/8	322	none
Lansing	Oil	3670	3678	5 1/2"	4234	3031

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 4253', ran sand to 4225' and ran 5 sacks cement.  
Shot pipe at 3196', 3010', pulled 94 joints. Pumped 2 sacks hulls, 15 sacks gel and 100 sacks cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 9 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of February, 19 73

My commission expires  
MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

Margaret Melcher  
Notary Public.

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

JAN 12 1971

HARVINA REISSIG 2-D  
 910' E of WL & 710' S of NL of NE/4  
 Sec. 23-25S-13W  
 Stafford County, Kansas

Commenced: December 23, 1970  
 Completed: January 6, 1971

OPERATOR - Clinton Oil Company

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 1 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas

DEPTH		FORMATION	REMARKS
From	To		
0	115	Sand and clay	
115	762	Red bed and shale	Ran 9 joints of 8-5/8" casing set @ 322' w/320 sacks cement.
762	778	Anhydrite	
778	1500	Shale	
1500	1675	Shale and shells	
1675	1920	Shale and lime	
1920	2460	Lime and shale	
2460	2820	Shale and lime	
2820	2999	Lime and shale	
2999	3190	Shale and lime	
3190	3305	Lime and shale	
3305	3470	Lime	
3470	3655	Lime and shale	
3655	4100	Lime	
4100	4148	Chert	
4148	4160	Lime and shale	
4160	4240	Lime	
4240	TD		Ran 132 joints of 5-1/2" casing set @ 4234' w/175 sacks cement.

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Well Log for the well drilled in the 910' E of WL & 710' S of NL in NE/4 Section 23-25S-13W, Stafford County, Kansas to the best of my knowledge and belief.

*James S. Sutton, II*  
 James S. Sutton, II

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 8th day of January, 1971, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

*Barbara J. Layton*  
 Barbara J. Layton, Notary Public

My Commission Expires February 1, 1972.

