

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15,185-22,212-0000

LEASE NAME Reissig

WELL NUMBER "A" #1

4950 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 23 TWP. 25 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed \_\_\_\_\_

Plugging Commenced 4-25-88

Plugging Completed 9-20-88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Pintail Properties

ADDRESS 412 E. Douglas, Suite #1, Wichita, Ks. 6720

PHONE# (316-263-2266) OPERATORS LICENSE NO. 5086

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 8, 1988 (date)

by Paul Luthi (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4274'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	392'	None
				5-1/2"	4250'	2,246.75'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Dumped sand to 3625' and 5 sacks cement. Shot casing at 3300', 2900', 2700' and 2200'. Pulled 63 joints of 5-1/2" casing. Howco squeezed well with 300# hulls, 10 sacks gel, 50 sacks 60/40 pozmix cement with 6% gel, 10 sacks gel, 100# hulls, released plug and pumped 125 sacks cement. Max pressure was 800 psi, shut in 800 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. \_\_\_\_\_

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Properties

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gr. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3rd day of October, 1988

Iona M. Leatherman

My Commission Expires: \_\_\_\_\_

STATE NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 4-26-91

Notary Public