

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford

County. Sec. 23 Twp. 25 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines. NE SW NE

Lease Owner Welch & Olsson Drilling Co. Inc.

Lease Name Leiss Well No. #2

Office Address 203 Rule Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 9-19-56

Application for plugging filed 9-19 19 56

Application for plugging approved 9-19 19 56

Plugging commenced 9-19 19 56

Plugging completed 9-19 19 56

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage, Box 283, Hoisington, Ks.

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4250 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	240.36'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 220'. Set plug and added half sack of hulls. Cemented with 20 sacks of cement. Mudded to 35' set plug and added one-third sack of hulls, and cemented with 10 sacks of cement.

Name of Plugging Contractor Welch & Olsson Drilling Co. Inc.
Address 203 Rule Bldg. Wichita, Kansas.

STATE OF Kansas COUNTY OF Sedgwick, ss.
R. E. Welch (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
203 Rule Bldg. Wichita, Kansas.

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 56

My commission expires June 12, 1959

Edith Erker Notary Public.

PLUGGING
FILE SEC. 23 T. 25 R. 13W
BOOK PAGE 101 LINE 19

SEP 20 1956
9-26-56
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG.

WELCH & OLSSON DRILLING CO. INC.

Elevation: 1926 R.B.

CONTRACTOR: WELCH & OLSSON DRILLING CO. INC.

Commenced Drlg: 9-6-56

LEISS #2

Completing Drlg: 9-19-56

NE SW NE of Section 23-25-13W, Stafford County,
Kansas.

Production: D & A.

Casing Record.

Set 240.36' of 8 5/8" with 200 sacks of cement.

(Figures indicate bottom of formations.)

<u>FORMATIONS</u>	<u>DEPTHS.</u>	<u>FORMATION TOPS.</u>	
Shale:	240	Heebner:	3471 -1545
Red Bed & Clay:	395	Toronto:	3488 -1562
Red Bed W/sand streaks:	450	Douglas:	3513 -1587
Red Bed & Shale:	790	Brown Lime:	3623 -1697
Anhydrite:	806	Lansing-Kansas City:	3647 -1721
Shale & Shells:	1540	Base Kansas City:	3917 -1991
Shale & Shells & Lime Strks:	1795	Marmaton:	3941 -2015
Shale & Lime:	3210	Conglomerate Shale:	4011 -2085
Lime:	3305	Conglomerate Chert:	4037 -2111
Lime & Shale:	3435	Viola:	4088 -2162
Lime:	3520	Simpson:	4187 -2261
Lime & Shale:	3685		
Lime:	4134		
Sand:	4250 T.D.		

STATE OF KANSAS,)
) SS:
SEDGWICK COUNTY,)

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the NE SW NE of Section 23, Township 25, Range 13 West, Stafford County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.

BY 
R. E. WELCH

Subscribed and sworn to before me this 24th day of September, 1956.


Edith Erker, Notary Public.

My commission expires:
June 12, 1959.

RECORDED
SEP 26 1956
COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 23 T. 25 R. 13W
BOOK PAGE 101 LINE 19