

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 20 Twp. 25 Rge. 13 (E) (W)  
NW SE NE

Location as "NE/CNW4SW4" or footage from lines  
Lease Owner Chief Drilling Company  
Lease Name Kipp Well No. 1  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 3/3/67 19\_\_\_\_  
Plugging completed 3/16/67 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elvin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4370 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	301	none
				5 1/2	4369	3025

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked bottom, ran sand to 4300', dumped 5 sacks of cement with 3" bailer. Cleaned cellar, rigged up on 5 1/2", had 20" tension. Shot pipe at 3535', worked pipe to 27", hooked up pump. Pumped 60 barrels of oil, chased plug. Plug stopped at 2640', racked pump, worked pipe to 29" tension. Let pipe set on tension. Fished plug out of hole, checked bottom. Got down to 3026', shot pipe at 3026', worked pipe loose and pulled 40 joints of 5 1/2". Pulled 54 joints of 5 1/2", had trouble with slips. Pipe was muddy. Set 10' rock bridge at 280' and dumped 5 sacks of cement. Tried to bail hole, got down to 210', could not bail hole down. Had welder cut off braden head and weld on 8 5/8 slip collar. Pumped 10 sacks of gel mud and 80 sacks of cement.

PLUGGING COMPLETE.

RECEIVED  
MAR 20 1967  
KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of March, 19 67

My commission expires February 15, 1971

Margaret Melcher  
Notary Public.

WELL LOG

STATE OF KANSAS  
MAR 6 1967  
OIL & GAS DIVISION  
Wichita, Kansas

Chief Drilling Co., Inc., etal.  
P.O. Box 97  
Great Bend, Kansas

#1 Kipp  
NW SE NE Sec. 20-25S-13W  
Stafford County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 7/25/60  
Completed: 8/10/60

Casing Record: 8 5/8" @ 301' cemented with 285 sacks cement.  
5 1/2" @ 4369' cemented with 35 sacks pozmix cement and 600 gallons latex cement.

FORMATION

From

To

ELEVATION

Sand & Shale	0	301
Redbed	301	425
Sand & Shale	425	822
Anhydrite	822	840
Shale & Shells	840	1240
Pyrite	1240	1242
Shale & Shells	1242	1270
Shale	1270	1790
Shale & Lime	1790	1975
Lime	1975	2580
Lime & Shale	2580	2790
Shale & Shells	2790	3290
Lime	3290	3530
Shale & Lime	3530	3570
Shale	3570	3682
Lime & Shale	3682	3714
Lime	3714	3995
Lime & Shale	3995	4079
Chert & Shale	4079	4157
Chert & Lime	4157	4259
Sand	4259	4290
Shale	4290	4322
Dolomite	4322	4370
Total Depth	4370	

FORMATION TOPS

Anhydrite	822 (+1129)
Heebner	3530 (-1579)
Brown Lime	3682 (-1731)
Lansing	3714 (-1763)
Base Kansas City	3995 (-2044)
Mississippi	4079 (-2128)
Viola	4157 (-2206)
Simpson	4259 (-2308)
Arbuckle	4322 (-2371)
Total Depth	4370 (-2419)

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NW SE NE Sec. 20-25S-13W, Stafford County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*V. Richard Hoover*  
V. Richard Hoover - President

Subscribed and sworn to before me this 10th day of August, 1960.

My commission expires:  
6/18/63

*Dorothy B. John*  
Dorothy B. John, Notary Public