


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 20 Twp. 25 Rge. 13 (E) (W)
Location as "NE/CNW&SW" or footage from lines NW SE NE
Lease Owner Chief Drilling Company
Lease Name Kipp Well No. 2
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 3/9/67 _____ 19____
Plugging completed 3/16/67 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elvin
Producing formation _____ Depth, to top _____ Bottom _____ Total Depth of Well 4435 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9 5/8	288	none
				7"	4390	2138

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 4250', dumped 7 sacks of cement with dump bailer, 3".
Cleaned cellar, rigged up on 7", pulled collar off L.J., trying to break loose
slips, in braden head. Had welder strap on collar, rigged up on 7", loaded hole,
shot pipe at 2530', worked pipe to 32", pipe parted down hole, 45', pulled pipe
out. Fished pipe, took tension on pipe. Shot pipe at 2134', worked pipe loose
and pulled 11 joints. Put ~~na~~ stinner on pole, hooked up oil line. Pulled
29 joints of 7", had trouble with slips, pipe breaking hard. Took pump to
lease. Pulled 25 joints of 7", had trouble with slips. Cleaned cellar, took braden
head off. Put 9 5/8 swedge on pipe. Hooked up pump, pumped 100 sacks of cement
and 10 sacks of mud. Talled pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1967

(If additional description is necessary, use BACK of this sheet.)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of March, 19 67

My commission expires February 15, 1971
Margaret Melcher
Notary Public.

WELL LOG

Chief Drilling Co., Inc. etal.
P. O. Box 97
Great Bend, Kansas

No. 2 Kipp
SW SE NE Sec. 20-25S-13W
Stafford County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 1-2-61
Completed: 1-20-61

Casing Record: 9-5/8" @ 288' cemented with 285 sacks Sunset Cement
7" @ 4390' cemented with 600 gallons Latex Cement and
50 sacks Pozmix Cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand and Shale	0	660'	1947' Gr.
Shale and Shells	660'	824'	1949' D.F.
Anhydrite	824'	840'	1952' K.B.
Redbed	840'	1335'	
Shale and Shells	1335'	1720'	
Shale with Lime Streaks	1720'	1790'	
Shale and Lime	1790'	1930'	
Lime and Shale	1930'	2070'	
Lime	2070'	2160'	
Lime and Shale	2160'	2610'	
Shale with Lime Streaks	2610'	2710'	
Shale and Lime	2710'	3085'	
Lime and Shale	3085'	3195'	
Shale and Lime	3195'	3290'	
Lime	3290'	3360'	
Lime and Shale	3360'	3440'	
Lime	3440'	3640'	
Shale and Lime	3640'	3710'	
Lime	3710'	4095'	
Lime and Shale	4095'	4147'	
Lime and Chert	4147'	4250'	
Sand	4250'	4282'	
Shale, Dolomite and Sand	4282'	4317'	
Dolomite	4317'	4435'	
Total Depth	4435'		

<u>FORMATION TOPS:</u>	
Anhydrite	824' (+1128)
Heebner	3524' (-1572)
Brown Lime	3677' (-1725)
Lansing	3709' (-1757)
Base Kansas City	3984' (-2032)
Viola	4147' (-2195)
Simpson	4250' (-2298)
Arbuckle	4317' (-2365)
Total Depth	4435' (-2483)

RECEIVED
MAR 6 1967
GEOLOGICAL SURVEY DIVISION

STATE OF KANSAS, COUNTY OF BARTON) SS.

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SW SE NE Sec. 20-25S-13W, Stafford County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 23rd day of January, 1961.

My commission expires: October 3, 1964.

Helen E. Fischer
Helen E. Fischer, Notary Public