

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

11-16-66

Operator's Full Name Walters Drilling Company & Oil Property Management, Inc.

Complete Address: 400 Insurance Bldg., Wichita, Kansas

Lease Name Thacher Well No. # 1

Location SW SW SW Sec. 34 Twp. 25 Rge. 11 (E) W

County Stafford Total Depth 4400'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Walters Drilling Company

Address: 400 Insurance Bldg., Wichita, Kansas License No.

Operation Completed: Hour 9:30AM Day 15th Month Nov. Year 1966

The Above well was plugged as follows:

248' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 230', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 230', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole br-
idged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 11/16/66

INV. NO. 4294-U