

Form CP-3
Rev. 6-26-62

4 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Continental Oil Co.

Complete Address: Box 267, Great Bend, Kansas

Lease Name Riley Well No. # 1

Location SE SE SE Sec. 32 Twp. 25 Rge. 11 (E) (W) W

County Stafford Total Depth 4350

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Western Petroleum Co. Inc.

Address: 925 Patton Road, Great Bend, Kansas License No.

Operation Completed: Hour 5:00PM Day 11th Month Nov. Year 1963

The Above well was plugged as follows:

250' of 10 3/4" surface pipe, cemented with 300 sacks. Fluid level was
up in hole, 1st cementing plug and 1/4 sack hulls was pushed to 240',
cemented with 30 sacks, through the drill pipe. Hole was filled with
drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack hulls,
cemented with 15 sacks to base cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/15/63
INV. NO. 8111-11

Signed: Archie Elving
Well Plugging Supervisor