

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

15-047-06075-0000  
API NUMBER NA

LEASE NAME Bryant

WELL NUMBER 1

3630 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 2 TWP. 26 RGE. 16 ~~XX~~ or (W)

COUNTY Edwards

Date Well Completed 11-5-58

Plugging Commenced 8-4-92

Plugging Completed 3:45 PM

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Great Bend Casing Pullers, Inc.

ADDRESS P.O. Box 251, Great Bend, Kansas 67530

PHONE# (316) 793-9711 OPERATORS LICENSE NO. 4635

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-4-92 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? NA If not, is well log attached? NA

Producing Formation NA Depth to Top 3944 Bottom 3950 T.D. 4423

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	415	0
				5 1/2	4418	2198

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from feet to feet each:

Bottom plug: Sanded to 3890 & bailed 5 sx Cement.

Top plug: Pumped 300 lbs Hulls, 10 sx Gel, 50 sx Cement, 10 sx Gel, 100 lbs

Hulls, 8 5/8 Wiper plug, 125 sx 60/40 6% Gel. Had Maximum pressure of 150 lbs & 50 lbs shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Bend Casing Pullers, Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Gary G. Burke

(Employee of Operator) or (Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke Pres

(Address) Box 251, Great Bend, Kansas 67530



SUBSCRIBED AND SWORN TO before me this 5 day of August, 1992

Anna K. Burke AUG 6 1992

Notary Public

My Commission Expires: 4-30-96

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
Form C1  
Revised 05