

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-047-10026-0000

API NUMBER _____

LEASE NAME Wood

WELL NUMBER #2

SPOT LOCATION SW SW NE

SEC. 2 TWP. 26 RGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed _____

Plugging Commenced 6-24-86

Plugging Completed 6-27-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS 801 Union Center Wichita, Kansas 67202

PHONE # (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Didge City, Kansas

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	425'	none
				5-1/2"	4449'	2527'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 4400' and 5 sacks cement. Shot pipe @3000', 2700', 2527', pulled a total of 87 joints of 5-1/2" casing. Plugged surface with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug and 125 cement, 60/40 pos, 6% gel. Plugging Complete
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso, President (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 30 day of June, 19 86



Irene Hoover
Notary Public

My Commission expires: _____

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
608 East Murdock, Wichita, Kansas


COPY

Company. CRAWFORD OIL & GAS RESERVE
Farm. Wood No. 2

SEC. 2 7, 26 R. 16W
SW SW NE

Total Depth. 4450'
Comm. 4-21-61 Comp. 5-1-61
Shot or Treated.
Contractor. Prime Drilg. Co.
Issued. 8-17-63

County Edwards
KANSAS



CASING:
8 5/8" 425' cem w/275 sx.
5 1/2" 4449' cem w/75 sx.

Elevation. 2054' RD

Production. 35 BOPD

Figures Indicate Bottom of Formations.

sand	240
sand & shells	427
shale, shells & sand	1040
anhydrite	1065
shale & shells	2040
lime	2435
shale & lime	2575
lime & shale	2845
shale & lime	3205
lime & shale	3290
shale & lime	3455
lime	3540
lime & shale	3665
lime	3762
lime & shale	3904
shale	3910
lime	4190
lime & shale	4290
shale & lime	4380
lime	4450 RTD
Total Depth	

TOPS: SCOUT	
Anhydrite	1040
Base Anhydrite	1065
Heebner	3746
Toronto	3764
Douglas	3780
Brown Lime	3899
Lansing	3910
Base Kansas City	4167
Fort Scott	4341
Cherokee Shale	4358
Conglomerate	4388
Kinderhook Shale	4397