

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Edwards SEC. 2 TWP. 26S RGE. 16W E/W  
Location as in quarters or footage from lines:

NW SW NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner Oil Properties Co. Inc.

Lease Name Cudney #1 Well No. \_\_\_\_\_

Office Address Box 335, Andover, Ks. 67002

Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_

Date Well Completed \_\_\_\_\_

Application for plugging filed \_\_\_\_\_

Plugging commenced 3/27/81

Plugging completed 3/31/81

Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4443

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	429	None
				4-1/2"	4440	3478'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

~~Moved in. Made bottom hole plug back with sand to 4000'. Mixed and ran 4 sacks cement thru dump baler. Pulled 18" tension. Made shots at ~~XX~~ 3840 and 3710. Tension 22 1/2 min and 31 1/2 max. Made shots at ~~XXX~~ 3615 and 3480. Worked pipe free and pulled total of 95 joints. Squeezed hole with 15 sacks gel, 6 sacks hulls and 10 sacks gel. Released plug and displaced with 125 sacks 50/50 pos 4% gel 3% cc. Plugging complete.~~

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS


RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 19 81

My Commission expires \_\_\_\_\_



Joan Kelso  
Notary Public.