


15-047-10021-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



EDWARDS County. Sec. 3 Twp. 26 Rge. 16W (E) (W)
Location as "NE/CNW/SW" or footage from lines. C S/2 N/2 NW
Lease Owner SANTA FE PIPE & SUPPLY
Lease Name REID Well No. 1
Office Address P. O. BOX 562 - GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed SEPTEMBER 6 19 58
Application for plugging filed APPLIED FOR VERBALLY BY 19
Application for plugging approved GLENN & SMITH 19
Plugging commenced SEPTEMBER 12 19 61
Plugging completed SEPTEMBER 17 19 61
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. FRANK BROADFOOT
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4485' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	395'	NONE
				4 1/2	4494'	3910'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4458'	-	4000'	-	SAND
4000'	-	300'	-	MUD
300'	-	290'	-	ROCK BRIDGE
290'	-	230'	-	20 SACKS CEMENT
230'	-	35'	-	MUD
35'	-	BASE	-	10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GLENN & SMITH PIPE PULLING COMPANY
Address P. O. BOX 114 - ELLINWOOD, KANSAS


STATE OF KANSAS, COUNTY OF BARTON, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 562, GREAT Bend, Ks
(Address)

SUBSCRIBED AND SWORN to before me this 16 day of DECEMBER, 1961

My commission expires May 19 1962

[Signature]
Notary Public.



15-047-10021-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company: CHIEF DRILLING CO. - HUDSON ET AL
Farm: Reid No. 1

SEC. 3 T. 26 R. 16W
C 5/2 N/2 NW

Total Depth. 4485'
Comm. 8-23-58 Comp. 9-6-58
Shot or Treated.
Contractor. Chief Drig. Co.
Issued: 3-21-59

County Edwards
KANSAS



CASING:
8 5/8" 395' cem w/350 sx.
4 1/2" 4494' cem w/150 sx.

Elevation. 2070' DF

Production. 2,125,000 CBG

Figures Indicate Bottom of Formations.

sand & clay	315
shale	395
shale & red bed	600
shale, red bed & sand	1069
Anhydrite	1084
red bed, shale & shells	1385
shale	1735
shale & lime	1980
lime	2540
shale & lime	2975
shale & shells	2190
shale & lime	3530
lime	4485 RTD
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1961

CONSERVATION DIVISION
Wichita, Kansas

TOPS:	
Anhydrite	1069
Heebner	2756
Brown Lime	3899
Lansing	3915
Cherokee Shale	4366
Cherokee Sand	4371
Cherty Conglomerate	4400
Kinderhook Sand	4460