

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15,047-20,449-0000

LEASE NAME Wood

WELL NUMBER "A" #1

1980 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 2 TWP. 26 RGE. 16 (E) or (W)

COUNTY Edwards

Date Well Completed _____

Plugging Commenced 12-29-87

Plugging Completed 1-26-88

LEASE OPERATOR Oil Producers Inc. of Kansas

ADDRESS Box 8647, Wichita, Ks. 67208

PHONE# 316-672-3440 OPERATORS LICENSE NO. 8061

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	420'	None
				4-1/2"	4449'	3,435.40'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4330' and 4 sacks cement. Shot casing at 4000', 3800' and 3400'. Pulled 85 joints of 4-1/2" casing. Halliburton squeezed well with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and pumped 125 sacks 60/40 pozmix cement with 6% added gel. Maximum pressure was 400 psi and shut in 150 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. STATE CORPORATION COMMISSION

Address Box 698, Great Bend, Ks. 67530 1-28-88 8 1988

STATE OF Kansas COUNTY OF Barton, ss.

CONSERVATION DIVISION

James W. Rockhold (Employee of Operator) or Wichita, Kansas of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 27th day of January, 19 88

Iona M. Leatherman

STATE NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-91

My Commission Expires:

Notary Public