

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20,747-0000

LEASE NAME Cudney

WELL NUMBER "A" #3

4950 Ft. from S Section Line

2240 Ft. from E Section Line

SEC. 2 TWP. 26 RGE. 16 (E) or (W)

COUNTY Edwards

Date Well Completed _____

Plugging Commenced 5-25-89

Plugging Completed 6-29-89

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS Box 8647, Wichita, Kansas 67208

PHONE# (316-672-3440) OPERATORS LICENSE NO. 8061

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 29, 1989 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	452'	None
				4-1/2"	4476'	3,215.30'

RECEIVED
STATE CORPORATION COMMISSION

JUL -7 1989

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4312' and 4 sacks cement. Shot casing at 3800', 3500' & 3200'. Pulled 100 joints of 4-1/2" casing. Allied plugged well with 400# hulls, 10 sacks gel, 50 sacks cement 10 sacks gel, 100# hulls released plug and pumped 125 sacks 60/40 poz mix cement with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers, Inc. of Kansas

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 6th day of July, 1989

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. Feb 91

Iona M. Leatherman
Notary Public

My Commission Expires _____