

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED Form CP-4
STATE CORPORATION COMMISSION
REV. 12-15-80

JUN 21 1982


CONSERVATION DIVISION
Wichita Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 2 TWP. 26S RGE. 16W E/W
Location as in quarters or footage from lines:

SE NE SW



Lease Owner Oil Properties Company, Inc.

Lease Name Bryant X-2 Well No. _____

Office Address Box 335 Andover, Kansas 67002

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 5-26-82

Plugging completed 6-2-82

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom T.D. 4466'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				13-3/8"	128'	none
				8-5/8"	424'	none
				4-1/2"	4461'	3549'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 4330' and ran 4 sacks cement. Shot casing @4040, 3926', 3801', 3650' and 3530'. Pulled a total of 111 joints of 4-1/2" casing.

Plugged well with 5 sacks hulls, 25 sacks gel, 8-5/8" plug, 140 sacks 50/50 pos, 2% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June, 19 82



My Commission expires:

Irene Hoover
Notary Public.

Phone 913-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

Phone Plainville 913-434-2812
 Phone Kiowa 316-825-4618

ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31.

Russell, Kansas 67665

No 28128

Date	10-2-82	Sec.	Twp.	Range	Called Out	On Location	Job Start	Finish	
					8:00am	10:15am	12:00pm	1:00pm	
Lease	Brumfi	Well No.	2			Location	Turntable 1/2 S 2 1/2 E 10 W	County	Edwards
							State	KS	

Contractor		Kelan Casing	
Type Job		Abandon Plug	
Hole Size	7 7/8	T.D.	
Csg. Size	4 1/2	Depth	
Tbg. Size		Depth	
Drill Pipe		Depth	
Tool		Depth	
Cement Left in Csg.		Shoe Joint	
Press Max.	100	Minimum	
Meas Line		Displace	
Perf.			

Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.
Charge To	Oil Property Co Inc
Street	Box 8147
City	Winchita, State KS.
The above was done to satisfaction and supervision of owner agent or contractor.	

Purchase Order No.
 x Bill Full @ Kelan Casing Pulling
CEMENT

EQUIPMENT		
Pumptrk	No 80	Cementor
		Helper
Pumptrk	No 101	Cementor
		Helper
Bulktrk		Driver
Bulktrk		Driver

Amount Ordered	140s x 5/8 370cc 2 1/2	
Consisting of	25 x 2 1/2 5 x Hulle	
Common	70 x	4.75 332.50
Poz. Mix	70 x	1.85 129.50
Gel.	285 x	10.25 175.00
Chloride	55 x	20.00 100.00
Quickset		
Hulle 55 x	14.00	70.00
		Sales Tax

DEPTH of Job		
Reference:	Pumptrk	340.00
	Plus	10.00
	53 miles	53.00
	Sub Total	
	Tax	
	Total	403.00

Handling	178 x	.90	160.20
Mileage	53 miles	.60	272.14
		Sub Total	
		Total	1239.34
Floating Equipment			

Remarks:
 on road 5 Hulle, 25 x 2 1/2, Plug 140s, 5/8 370cc 2 1/2 Hulle.
 Thermo