

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,178-050

LEASE NAME Woods #4

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C SE SE NE

SEC. 2 TWP. 26 S RGE. 16 W (E) or (W)

COUNTY Edwards

Date Well Completed 6/19/84

Plugging Commenced 3/11/85

Plugging Completed 3/14/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS 801 Union Center, Wichita, Ks. 67202

PHONE # (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4455'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13 3/8	110'	none
				8 5/8	473'	none
				5 1/2"	4453'	3055'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4350' & 5 sacks cement. Shot pipe at 3506', 3217', and 3055'. Pulled 97 joints of pipe. Plugged well with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, released plug, & 150 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 19th day of March, 1985



My Commission expires: \_\_\_\_\_

Irene Hoover  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 20 1985  
CONSERVATION DIVISION  
Wichita, Kansas