

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,156-000

LEASE NAME Cudney "A"

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 4  
280' FNL & 510' FEI  
SPOT LOCATION of NE/4

SEC. 2 TWP. 26S RGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed 3/7/84

Plugging Commenced 3/7/84

Plugging Completed 3/7/84

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS P.O. Box 8647, Wichita, Kansas 67208

PHONE (316) 681-0231 OPERATORS LICENSE NO. 8061

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? #1, Dodge City, KS

Is ACO-1 filed? To be filed. If not, is well log attached? Yes

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	338'	8-5/8"	331'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged with 50 sacks cement at 960';  
50 sacks cement at 420'; solid bridge plug  
and 10 sacks cement at 40'; 15 sacks cement  
in rat hole. (60-40 Pozmix cement, 3% Gel, 2% Calcium Chloride.)


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor The Buie Co. License No. \_\_\_\_\_

Address N. Highway 281, Pratt, KS 67124

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John D. Knightley, Agent (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as RECEIVED that the same are true and correct. So help me God.



STATE CORPORATION COMMISSION

APR 10 1984

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) [Signature]  
221 S. Broadway, Suite 400  
(Address) Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 21st day of March, 1984

Stella J. Lips  
Notary Public

My Commission expires: March 12, 1987

Oil Producers, Inc. of Kansas  
P.O. Box 8647  
Wichita, Kansas 67208

Cudney "A" #4  
280' FNL & 510' FEL of NE/4  
Section 2-26S-16W  
Edwards County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.  
221 S. Broadway, Suite 400  
Wichita, Kansas 67202

Commenced: February 29, 1984  
Completed: March 7, 1984

Drillers Log

Sand	380
Red Bed	1054
Anhydrite	1067
Shale	2115
Shale & Shells	2380
Shale & Lime	2650
Shale	2900
Shale & Shells	3140
Lime & Shale	3625
Shale & Lime	3795
Lime	4460 RTD

Casing: 338' 8-5/8" cemented with 200 sacks Class H Cement,  
3% Calcium Chloride.

RECEIVED  
STATE CORPORATION COMMISSION

APR 10 1984

CONSERVATION DIVISION  
Wichita, Kansas