


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.,
Wichita, Kansas

15-047-00097-0000

TP

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Edwards County, Sec. 3 Twp. 26 Rge. 16 (E) W (W)
Location as "NE/CNW/SW" or footage from lines: C NW/4 SE/4
Lease Owner: Henry S. Inger
Lease Name: Schultz Well No. 1
Office Address: Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole):
Date well completed: 19____
Application for plugging filed: 19____
Application for plugging approved: 19____
Plugging commenced: 7-10-61 19____
Plugging completed: 7-13-61 19____
Reason for abandonment of well or producing formation: Depleted.

If a producing well is abandoned, date of last production: 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Frank Broadfoot.
Producing formation: Depth to top: Bottom: Total Depth of Well: 4450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	295'	None
				5-1/2"	4450'	3595'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4384', sanded to 4350', and dumped 5 sacks of cement @ 4350' with dump bailer. Pulled 5 1/2" casing. Bailed hole to 240', set 10' rock bridge to 230' and ran 20 sacks of cement @ 230'. Mudded hole to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: Knight Casing Pulling Company
Address: Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 1961

My commission expires May 20, 1964

Milton J. Volin
Notary Public.



WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-047-00097-0000
COPY

Company- R. T. LEEPER
Farm- Schultz No. 1

SEC. 3 T. 26 R. 16W
C NW SE

Total Depth. 4450'
Comm. 4-15-59 Comp. 7-24-59
Shot or Treated.
Contractor. L. C. Smitherman
Issued. 6-17-61

County Edwards
KANSAS



CASING:
8" 275'
5" 4441'

Elevation. 2067' RB
Production. 2,000,000 CFG

Figures indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE;

TOPS: SCOUT
Haebner 3750
Toronto 3770
Douglas 3790
Brown Lime 3897
Lansing 3920
Base Kansas City 4175
Cherokee Sand 4368
Mississippi 4384
Kinderhook Sand 4437

Total Depth 4450

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 1962

CONSERVATION DIVISION
Wichita, Kansas