

WELL PLUGGING RECORD

Stafford County. Sec. 3 Twp. 25 Rge. (E) 14 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ SE $\frac{1}{4}$ NE $\frac{1}{4}$

Lease Owner White Eagle Oil Co.

Lease Name Dykes Well No. 1

Office Address First National Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-17- 19 53

Application for plugging filed 5-17- 19 53

Application for plugging approved 5-17- 19 53

Plugging commenced 5-17- 19 53

Plugging completed 5-17- 19 53

Reason for abandonment of well or producing formation

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Show depth and thickness of all water, oil and gas formations.

CASING RECORD

[illegible]

1st Plug @ 250' with 20 Sx Cement & 1/2 Sx Halls
2nd Plug @ 35' with 10 Sx Cement on Top

Name of Plugging Contractor. Lewis Drilling Company
Address 607 Union National Bank Building, Wichita, Kansas

(Signature) *R. H. Duley*
607 Union National Bank Bldg., Wichita, Kansas
 (Address)

23-8390-s 6-51-20M

PLUGGING
FILE SEC 9 T 25 R 14W
BOOK PAGE 102 LINE 60

MAY 26 1953
 RECEIVED
 THE COMPTROLLER OF THE CURRENCY
 MAY 26 1953
 CONSERVATION DIVISION
 Wichita, Kansas
 Notary Public.
 5-26-53

WELL LOG

COMPANY White Eagle Oil Co.

SEC. 3 T. 25 R. 14W

FARM Dykes

NO. 1

LOC. SW $\frac{1}{4}$ SE $\frac{1}{4}$ NE $\frac{1}{4}$

TOTAL DEPTH 4303'

COMM. 4-30-53


COMP. 5-17-53

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED

COUNTY Stafford
KANSAS



CASING


20	10	
15	XX	8-5/8" 250'
12	6	
13	5	

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0	=	150	Sand
150	=	225	Blue Shale
225	=	250	Red Bed
250	=	825	Red Bed & Sand
825	=	845	Red Bed
845	=	880	Anhydrite
880	=	1490	Salt & Shale
1490	=	1895	Lime & Shale
1895	=	2070	Br. Lime
2070	=	2210	Br. Lime & Shale
2210	=	2390	Br. Lime
2390	=	3140	Lime & Shale
3140	=	3225	Shale
3225	=	3698	Shale & Lime
3698	=	3747	Lime
3747	=	3875	Lime & Shale
3875	=	3920	Shale
3920	=	4022	Shale & Lime
4022	=	4025	Mississippi Chat
4025	=	4095	Lime & Shale (Cherty)
4095	=	4130	Viola Lime & Shale
4130	=	4170	Lime & Shale (Cherty)
4170	=	4235	Cherty Lime & Shale
4235	=	4283	Sandy Shale
4283	=	4303	Lime & Shale (Arbuckle)
4303	=		T.D.



STATE OF KANSAS
MAY 20 1953
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of SEDGWICK } ss:

I, L. L. Bailey of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Dykes #1 well.

L. L. Bailey

Subscribed and sworn to before me this 21 day of May 19 53

My Commission Expires: August 20, 1956

Arthur R. Derrington
NOTARY PUBLIC