

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-1

File All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217

Locate well correctly on above
Section Plat

WELL PLUGGING RECORD

/ Stafford County, Sec. 3 Twp. 25 Rge. 14 (E) W (W)
Location as "NE/CNWSW" or footage from lines 65' SE of SE 1/4 SW 1/4
Lease Owner Martin Oil & Gas Co. & Aspen Drilling Co.
Lessee Name WILSON Well No. 1-A
Office Address 4705 No. 32nd Place, Phoenix, Arizona 68108
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 17 19 74
Application for plugging filed July 17 19 74
Application for plugging approved July 17 19 74
Plugging commenced July 17 19 74
Plugging completed July 17 19 74
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Bieberstein
Producing formation Depth to top Bottom Total Depth of Well 4070 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud. cement thru
Set plug at 550' with 50 sacks/drill pipe.
Come up hole to 240' -set plug with 25 sacks cement thru d.p.
Set Plug at 40' with 1/2 sack hulls and 10 sacks cement
2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1974
CONSERVATION DIVISION
Wichita, Kansas

7-22-74

Name of Plugging Contractor Duke Drilling Co.
Address Box 823 - Great Bend, Ks. 67530

STATE OF Kansas

COUNTY OF Barton

ss.

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 823 - Great Bend, Ks. 67530

(Address)

19 74.

April 11, 1978

Notary Public.

DRILLERS' WELL LOG

DATE COMMENCED: July 8, 1974
DATE COMPLETED: July 17, 1974

Drillers' Log

0 - 135' Sand
135 - 225' Red Bed
235 - 300' Shale
300 - 655' Red Bed, Shale, Sand
655 - 869' Red Bed
860 - 870' Anhydrite
870 - 1035' Shale, Shells
1035 - 1735' Shale
1735 - 3180' Shale & lime
3180 - 3509' Lime
3509 - 3529' Shale & Lime
3529 - 3548' Lime
3548 - 3650' Shale
3650 - 3680' Br. Lime
3680 - 3934' Lime
3934 - 4032' Lime & Shale
4032 - 4044' Chert
4044 - 4070' Shale
4070' RTD

Martin Oil & Gas Co. &
Aspen Drilling Co.
WILSON 1-A
65' SE of SE/4 SW/4
Sec. 3-Twp.25,Rge.14,W
Stafford County, Kansas

ELEVATION: 1966 K.B.

FORMATION DATA (Elec Log)

Anhydrite	860
Topeka	3180
Heebner	3509
Toronto	3529
Douglas	3548
Brown Lime	3650
Lansing	3680
Base -Lansing (K.C.)	3934
Mississippi Chert	4032
Kinderhook Shale	4044
RTD	4070'

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1974
CONSERVATION DIVISION
Wichita, Kansas

SURFACE PIPE: Set used 28# 8-5/8"
at 296' with 225 sacks common, 2% Gel,
3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Wayne Dobbs, of lawful age, does swear and state that the facts and statements
herein contained are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 19th day of July 1974.

My Comm. Expires:
April 11, 1978

Wayne Dobbs
Dorothy M. Hague
Notary Public