

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

151

15-155-70507-0600

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Pratt SEC. 21 TWP. 26s RGE. 15w E/W
 Location as in quarters or footage from lines:
C W/2 NW NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner Texas Energies Inc.
 Lease Name Smith #1 Well No. _____
 Office Address P.O. Box 947, Pratt, Ks. 67124
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 4/14/83
 Plugging completed 5/12/83
 Reason for abandonment of well or producing formation _____

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Suthi
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4254'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	437'	none
				4 1/2"	4251'	1791'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Sanded bottom back to 3850' & pumped 4 sacks cement, Shot casing at 3009',
 2407', 2011', & 1804'. Pulled total of 41 joints of pipe, Plugged well
 with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, released plug & 120 sacks
 60/40 poz 3% gel 3% c.c.

Plugging complete.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of May, 19 83



My Commission expires: _____
Irene Hoover
 Notary Public.

MAY 16 1983

CONSERVATION DIVISION
 Wichita, Kansas